BRUHATH BANGALORE MAHANAGARA PALIKE,

Office of the Executive Engineer Dasarahalli Division,

Shedule-B

NAME OF WORK: Pothole Filling in Ward No.12 Shettyhalli, Shettyhalli Sub Division.

Sl. No	Description of work	Unit	Qty	Sanctioned rates	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Wet Mix Macadam KSRRB M400-17. Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density etc., complete as per specifications and as per the direction of Engineer-in-charge of the work.	Cum	288.54	2001.28	Rupees Two Thousand One And Paise Twenty Eight Only
2	Filling Pot-holes and patch repairs with bituminous concrete, 40 mm, KSRRB M3000-5, Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3 back filling the pot hole with bituminous material as per clause 500.4 compacting, trimming and finishing the surface to form a smooth continuous surfaceetc, complete as specifications and as per the direction of Engineer-in-charge of the work.	Cum	1923.57	365.70	Rupees Three Hundred Sixty Five And Paise Seventy Only

Executive Engineer
Dasarahalli Division

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palike
Dasarahalli Division, Bengaluru-73.